

The Trailer Factory
727196685
www.thetrailerfactory.ca
sales@thetrailerfactory.ca
519-228-8348

69613 Airport Line
Huron Park, Ontario N0M 1Y0
Canada



TRAILER FACTORY - ADA SKID
0340
Canada
andy@orrcompanyinc.com

Quote Number	QU1371
Quote Date	01-Jan-2024
Total	55,144.00 CAD

Item	Description	Unit Cost	Quantity	Line Total
------	-------------	-----------	----------	------------

Item	Description	Unit Cost	Quantity	Line Total
	<ul style="list-style-type: none"> • EXTERIOR: • ALUMINUM 8 ft 3 inch by 10 ft ft by 84" (interior height) • Dimensions may vary slightly • Floorplan drawings will be provided • 1x1.5 tube walls and cross members • 1x1 arched roof bows • All will be welded to the lower frame • 1 room plus mechanical room • One piece rubber membrane ceiling over ½" plywood on the curved roof trusses • 34" x 79" aluminum entry door with lockset – 1 of • INWARD swinging with aluminum frame • Door lever hand set – brushed aluminum • Heavy duty door closer • Drip rail installed above door • One additional door in the Service Room • 2 of 6" x 40" Aluminum tinted windows with screen • .030 seamless aluminum exterior cladding – Colour is WHITE • Screw-less install for smooth look • Water-tight exterior • 1 of exterior LED porch lights • 20 AMP, 240V Twist lock – inlet power • Powers heaters, water heater and lights • Service closet will have a light and 1000W heater 			
ACCESSIBLE SKID UNIT	<ul style="list-style-type: none"> • With thermostat • Heaters in main room will be 1 of 1000W wall mounted with trim rings • With thermostat • 2.5 Gallon electric 1440W water heater • Lower skid/frame was spray foamed • INTERIOR: • PVC GREY TREADPLATE style pattern flooring installed on top of aluminum plate floor • Porcelain AODA wall mounted sink • AODA levered faucet • Soap dispenser - wall mounted • Interior wall treatment is Fiberglass Reinforced panels – white • 1.5" insulation – R7.5 • Interior lighting is LED dome lights– 4 of • Mirror, wall mounted (tilted) – 1 of • Stainless steel or brushed aluminum paper towel holder and toilet paper holder • 1 of MANSFIELD ADA toilet - 1 HP macerator • Commercial toilet • Coat hooks included in each unit • AODA grab bars, hand holds etc as required 	36,500.00 CAD	1	36,500.00 CAD

Item	Description	Unit Cost	Quantity	Line Total
AODA kit	<ul style="list-style-type: none"> HU-LP-8-PUSH-39 - HUNTER LOW PROFILE OPERATOR – “Automatic Door Opener” WEC10K2 - CAMDEN EMERGENCY CALL KIT - “Emergency Call Button with Exterior Light and Siren” CD-WC13AXSM - CAMDEN BARRIER FREE WASHROOM KIT – “Illuminated Push Button Control Kit – Exterior: ‘Push to Open’ - Interior: ‘Push to Open/Push to Lock’ 	5,500.00 CAD	1	5,500.00 CAD
Accessories	<ul style="list-style-type: none"> Customer will install all accessories themselves (toilet paper holder, soap dispenser and paper towel dispenser) 	0 CAD	1	0 CAD
RAMP	<ul style="list-style-type: none"> AODA ramp attachment Aluminum built Clip in hand rails 6 ft in length (threshold height in unit is 6”) Grip step material installed on top panel 	4,950.00 CAD	1	4,950.00 CAD
AIRCONDITIONER	<ul style="list-style-type: none"> Install a Dometic 11,000 BTU airconditioner roof top mounted 	1,850.00 CAD	1	1,850.00 CAD
Certification	<ul style="list-style-type: none"> Unit will come with ESA approval and SN tag UNIT weight will be provided prior to completion - estimate 2900 pounds 	0 CAD	1	0 CAD

Quote Terms: 50% Deposit required, remaining payable upon delivery. Deposits are non-refundable on any cancellations. This constitutes a contract that the order has been placed. Credit card transactions subject to 2% surcharge Re-torque wheels to 100 ft/lbs at 100km	Net	48,800.00 CAD
	Subtotal	48,800.00 CAD
	HST 13%	6,344.00 CAD
	Total	55,144.00 CAD
	Paid to Date	0.00 CAD

Thank you for your business